



Bid Bulletin No. 004

MORE-BAC-2025-002
Development of 30/36 MVA Gen. Hughes Substation

Change in the Approved Budget for the Contract (ABC)

After further consideration, MORE Power Bids and Awards Committee (BAC) hereby resolves to change the approved budget for the contract (ABC) in accordance with the revised changes in the *Scope of Work* in the *Terms of Reference*:

1. Addition of one (1) unit 80-ft. self-supporting steel pole;
2. Addition of one (1) unit 50-ft. self-supporting steel pole; and
3. Additional construction of transformer firewall.

Upon consultation with the TWG, these revisions constitute an additional **PhP 6 Million** to the original ABC of PhP 55 Million.

Therefore, the following inclusions, revisions, amendments, and adoptions are made on the following provisions in the Bid Documents:

Document	From	To
<i>Invitation to Bid</i>		
Approved Budget for the Contract (ABC)	PHP 55,000,000.00 inclusive of VAT	PHP 61,000,000.00 inclusive of VAT
<i>Terms of Reference</i>		
Section III: Scope of Work, Item 2.2.1	Supply and Installation of 1 unit 80 ft Self Supporting Steel Pole. The Contractor shall supply and install 1 unit of 80 ft. Self-Support Steel pole including anchor bolts, climbing rungs, step bolts, cross-arms and other required accessories...	Supply and Installation of 2 units 80 ft Self Supporting Steel Pole. The Contractor shall supply and install 2 units of 80 ft. Self-Support Steel pole including anchor bolts, climbing rungs, step bolts, cross-arms and other required accessories...
(additional item) Section III: Scope of Work, Item 2.2.2	-	Supply and Installation of 1 unit 50 ft Self Supporting Steel Pole. The Contractor shall supply and install 1 unit of 50 ft. Self-Support Steel pole including anchor bolts, climbing rungs, step bolts, cross-arms and other required accessories needed to complete the installation in accordance with the requirements and specifications indicated in the Tender Documents and approved



MORE POWER

MORE ELECTRIC AND POWER CORPORATION

		plans and drawings. The Self-supporting steel pole shall four (4) circuits of 13.8kV primary lines.
<i>(additional item)</i> Section III: Scope of Work, Item 3.1.1.21	-	Supply, Delivery and Construction of a New Transformer Firewall. The Contractor shall supply, deliver and construct approx. 8-meter high transformer firewall including its foundation consisting of concrete (211 kg/cm ²), 6 inches CHB 600 psi, Reinforcing Steel Bars (grade 275), Excavation and backfilling, Levelling concrete (141 kg/cm ²), and other incidentals required to complete the works in accordance with the requirements and specifications indicated in the Tender Documents and approved plans and drawings.

The BAC further resolves that there shall be no changes in the contract duration, considering that the additional scope of work is not significant enough to affect the project timeline.

All terms, conditions and instructions to bidders specified in the Bidding Documents inconsistent with this Bid Bulletin are hereby superseded and modified accordingly.

Issued this 14th day of February 2025 in Iloilo City, Philippines.

Approved by:

ATTY. ELIZABETH DYHN A. CABUNAGAN
Chairperson
Bids and Awards Committee